

Review of the European XFEL Linac System

Cold Magnets and Vibrations

H. Brueck

DESY MKS

March 26, 2007

Topics

- Prototype magnets
- Prototype Leads
- Plans for testing at DESY
- Vibration measurements

Involved people so far are:


F. Toral, P. Abramian, J. Calero, L. García-Tabarés, J.L. Gutierrez,
E. Rodriguez, I. Rodríguez, S. Sanz, C. Vazquez, **CIEMAT-CEDEX, Spain**
J. Lucas, **Elytt-Energy, Madrid, Spain**

A. Ballarino, P. Denis, **CERN**

R. Bandelmann, Y. Bozhko, A. Zolotov, M. Stolper, J. Fischer, W. Shi, W. Maschmann,
H. Brueck, **DESY MKS**
N. Mildner, **DESY MVP**


XFEL Magnet and Lead Design

- Magnet at beam exit side
- BPM (not shown) flanged to magnet
- Magnet supported like cavities, connected to invar rod
 - Moves by about 3 cm when cooled down



Present XFEL Design


- Prototype Magnet and Lead assembly at DESY
- Stainless steel vessel
- Copper coated beam pipe
- Flange only to 2K He tube and to warm-up tube
- Conduction cooled current leads for 50A with two heat sinks at 4-8K and 40-80K
- CERN type
- No gas flow
- Heat loads at 50A (for each of the six leads)
 - 2.56 W/lead at 70 K,
 - 0.54 W/lead at 4.5 K,
 - 0.04 W/leads at 1.9 K
- At zero current load at 1.9 K will vary from 0.02 to 0.035 depending on the length



Magnet Package



Three nested
magnets

“super ferric”
quadrupole



Solid yoke for
prototype
magnets

“cos θ ” type
dipoles



Quadrupole Parameter

Iron yoke inner diameter	[mm]	94.4
Iron yoke outer diameter	[mm]	270
Nominal current	[A]	50
Nominal gradient	[T/m]	35
Magnetic length	[mm]	169.6
Number of turns		646 (34x19)
Wire diameter (bare/insulated)	[mm]	0.4/0.438
Copper to superconductor ratio		1.35
RRR		>70
Filament diameter	[micron]	35
Twist pitch	[mm]	50
Iron yoke length	[mm]	145
Coil length	[mm]	200.6
Stored magnetic energy at 50A	[J]	1462
Self inductance	[H]	1.17
Integrated gradient at 50A	[T]	5.976
Integrated b6 at 50A	$10^{-4} \times b_2$ at 30mm	-1.87
Integrated b10 at 50A	$10^{-4} \times b_2$ at 30mm	2.75
Coil peak field	[T]	2.48

Roxie and Ansys calculations

Quench model calculations show:

$$T_{\max} \sim 70\text{K}$$

$$U_{\max} \sim 70\text{V}$$

Working point on load line at 4.2K	[%]	40
Working point on load line at 2K	[%]	27
Saturation at 50 A (integrated)	[%]	~4

Dipole Parameter

Inner diameter	[mm]	83.6	88.5
Nominal current	[A]	50	50
Nominal field	[T]	0.04	0.04
Magnetic length	[mm]	203.7	205
Number of turns		36	37
Wire diameter (bare/insulated)	[mm]	0.7/1.03	0.7/1.03
Copper to superconductor ratio		1.8	1.8
RRR		>100	>100
Filament diameter	[micron]	<20	<20
Twist pitch	[mm]	25	25
Iron yoke length	[mm]	145	145
Coil length	[mm]	230	230
Self inductance	[mH]	0.96	1.07
Integrated field at 50A	[Tm]	0.00815	0.00820
Working point on load line at 4.2K	[%]	11.1	11.3
Working point on load line at 2K	[%]	7.9	7.9
Saturation at 50 A (integrated)	[%]	9	10

Roxie and Ansys calculations


- The **Working point** is rather low! (left over HERA cable)
 - large persistent current effects may show up
 - Proposal is to increase copper to superconductor ratio for next magnets

With Quad at 50A

Prototype Magnets


- Production of 4 magnets with He-vessels in collaboration with CIEMAT, Spain
- First magnet arrived end of December
 - Since then setup of measurement equipment and first warm measurements
 - Now waiting for a time slot in Hall 3 for cold tests in a vertical bath cryostat
 - Hope to finish early April

XFEL Warm Measurement Setup



- Setup for
 - Rotating Coil
 - Stretched Wire
- Closed hermetically by windows
- “4-wire” calibration magnet mounted to check harmonics coil

XFEL Warm Measurement Setup





Stretched Wire tables,
moved out

Harmonics coil with shaft
and step motor

4-wire calibration magnet

DC, Final Quad $\pm 0.17A$, earth file elimination



k =	a _f _k =	b _f _k =	c _f _k =
1	1.21	-21.46	21.49
2	0	10000	10000
3	10.12	-1.06	10.18
4	1.16	2.15	2.44
5	1.73	-0.82	1.91
6	0.15	-6.99	6.99
7	1.53	0.2	1.54
8	-0.02	0.11	0.11
9	-0.01	-0.01	0.02
10	0.24	-2.49	2.5
11	0.05	0.02	0.05
12	-0.04	0.03	0.05
13	-0.02	0.02	0.03
14	0.02	-0.26	0.26
15	-0.01	0.04	0.04
16	0.01	0.02	0.03

[A]

$$\text{curr}_{m_i} = \frac{c_{mm1R}}{10} = 3.612 \text{ mTm/A}$$

0.17
0.17



$$\frac{c_{mm1R}}{r0 \cdot 10} = 120.392 \text{ mT/A}$$

fn1 = "HA0_07032007_0948.res"

fn2 = "HA0_07032007_0954.res"



DC Final, Inner Dipole $\pm 2A$, earth file elimination



k =	a _k =	b _k =	c _k =
1	0	10000	10000
2	13.51	-11.85	17.97
3	-26.32	139.99	142.45
4	0.82	-5.65	5.71
5	6.63	-828.2	828.23
6	-1.82	2.12	2.79
7	-3.35	-28.97	29.16
8	-4.19	1.5	4.45
9	-1.22	17.76	17.8
10	-1.64	0.38	1.69
11	-0.1	-27.82	27.82
12	0.64	-0	0.64
13	-0.42	-5.25	5.27
14	0.06	0.27	0.28
15	0.08	0.06	0.1
16	-0.08	0.22	0.24

About 1/769 of quad at 30mm, if both at same current

[A]

curr_{m₁} = $\frac{c_{mm_{IR}}}{10} = 0.156 \text{ mTm/A}$



$\frac{c_{mm_{IR}}}{r0 \cdot 10} = 5.2 \text{ mT/A}$

fn1 = "HA0_07032007_0915.res"

fn2 = "HA0_07032007_0923.res"



DC Final, Outer Dipole $\pm 2A$, earth file elimination



k =	a _{f_k} =	b _{f_k} =	c _{f_k} =
1	0	10000	10000
2	2.35	-0.22	2.36
3	-5.37	78.17	78.35
4	-0.96	2.38	2.57
5	-12.05	-813.86	813.94
6	0.15	-0.19	0.24
7	-5.15	-39.53	39.87
8	-0.79	-1.29	1.51
9	1.31	20.68	20.72
10	0.75	0.49	0.9
11	-1.49	-18.28	18.34
12	0.21	0.48	0.52
13	-0.72	-4.56	4.61
14	-0.06	-0.08	0.1
15	-0.16	-0.05	0.17
16	0.03	0.04	0.05

[A]

$$\text{curr}_{m_1} = \frac{c_{mm_{1R}}}{10} = 0.157 \quad \text{mTm/A}$$

$$\frac{c_{mm_{1R}}}{r0 \cdot 10} = 5.232 \quad \text{mT/A}$$


fn1 = "HA0_07032007_0858.res"

fn2 = "HA0_07032007_0905.res"

Alignment and Mounting of BPM

- Axis and angle measurement with “stretched wire system” ([info](#)) at room temperature with small current
- DC signals not big enough, switched to AC, about 5Hz
- Required accuracy
 - 0.3 mm for axis offset
 - 3 mrad for roll angle
- Reference of magnetic centre and angle w. r. t. mechanical centre (left/right) using [reference plates](#) fixed by dowel pins
- Connection to the BPM
 - Using same reference plate for referencing on a milling machine
 - Drilling of dowel pin holes for exact mounting of the BPM
 - This allows arbitrary pairs of Quads and BPMs

Axis and Angle (x, y, α, η) Measurements using AC SW



- Stretched Wire system
- 0.1A AC current in Magnet
- Reproducibility good
 - $x \sim .003$ mm
 - $y \sim .006$ mm
 - $\alpha \sim .03$ mrad
 - $\eta \sim .03$ mrad
- Averages themselves not useful, tables were not finally aligned

$x_{a_i} =$	$x_{s_i} =$	$y_{a_i} =$	$y_{s_i} =$	$\alpha_{a_i} =$	$\alpha_{s_i} =$	$\eta_{a_i} =$	$\eta_{s_i} =$
0.458	0.002	0.055	0.004	-0.043	0.051	0.078	0.082
0.454	0.004	0.057	0.003	-0.078	0.015	0.047	0.085
0.461	0.005	0.058	0.004	-0.030	0.037	0.019	0.051
0.451	0.003	0.046	0.004	-0.093	0.023	0.008	0.105
0.453	0.001	0.041	0.002	-0.016	0.023	0.007	0.029
0.453	0.002	0.043	0.002	-0.037	0.038	0.005	0.053
0.456	0.000	0.046	0.001	-0.024	0.030	0.014	0.063
0.456	0.003	0.047	0.003	-0.011	0.029	0.026	0.041

$\text{mean}(x_a) = 0.455$ $\text{mean}(y_a) = 0.049$ $\text{mean}(\alpha_a) = -0.042$ $\text{mean}(\eta_a) = 0.026$
 $\text{stdev}(x_a) = 0.003$ $\text{stdev}(y_a) = 0.006$ $\text{stdev}(\alpha_a) = 0.028$ $\text{stdev}(\eta_a) = 0.024$


Cold Magnet Tests in H55

- Tests at 2K in horizontal cryostat of each magnet together with the lead assembly in H55, ready early next year
- Operation test
 - Quench safety
 - Measure transfer functions, saturation, cold harmonics...
- Special tests with a subset only (~10% of magnets)
 - Persistent current effects
 - Axis and angle stability tests, during excitation, effect of nested coils
- Using
 - Harmonic coil (to be ordered)
 - Stretched Wire
- Cold leak rates

Vibration Measurements Module 6 CMTB

cold

06.12.06 23:00-01:00




- Sensor at support shows lowest RMS_{2Hz} of 52 nm and 107 nm
- Sensors at pumping port show very large horizontal values ($RMS_{2Hz} = 352$ nm)
- Magnet
 - Multiplied by 3 because of cold sensitivity loss
 - horizontal sensor shows probably wrong signal, step at 50Hz indicates noise

Need re-measurement at next module

Vibration Measurements Module 6 CMTB

cold

21.12.06 23:00-01:00





- Large steps at 31.7 Hz in all signals
- Not seen on 6.12.06!

Need re-measurement at next module



Effects vs Time (23:00-01:00, no average)

21.12.06 23:00-01:00

10.12.06 23:00-01:00



horizontal



vertical

23:00

01:00

23:00

01:00

- Sometime large effects occur, peaks of RMS_{2Hz} of about 600 nm
- Due to peak at
 - 31.5Hz on 10.12
 - 26Hz on 21.12

Quad
Lower support
Pumping port
Survey platform

Vibration Measurements M6 CMTB



Summary

- Floor motion larger as at FLASH
- Signals at pumping port rather large especially the horizontal signal ($\text{RMS}_{2\text{Hz}}$ up to 350nm)
- **Warm** Quad motion larger as at TTF
- Horizontal quad sensor probably gives wrong results when module **cold**
- **Cold** vertical quad motion depends strongly on conditions in the CMTB
 - $\text{RMS}_{2\text{Hz}}$ often only about 95nm
 - Under certain conditions sometimes large motions ($\text{RMS}_{2\text{Hz}}$ factor 6 larger up to 600nm)
- Need more measurements on module 7
- Need more investigations to find correlation to environment conditions


End

Reference Plates


Referenzplatte 1
(Strahlaustrittseite)




* diese Maße bekommen einen Korrekturwert




Referenzplatte 1
(Strahleintrittseite)




fehlende Maße und Toleranzen
wie Referenzplatte 1




Warm AC Harmonics





- Coil and motor support fine tunable
- No magnetic material in SW tables



Warm AC Stretched Wire




- Rigid support table
- Moving table accuracy:
 - $\sim 5\mu\text{m}$ for 100mm move from reference point
 - x: $\sim 1.5\mu\text{m}$, y: $\sim 3.5\mu\text{m}$ hysteresis
 - $\sim 50\text{-}100\mu\text{rad}$ angle stability during move
- Reproducibility for stretched wire measurements about $10\mu\text{m}$ for x and y and about $10\mu\text{rad}$ for the angle




Current Leads

- Conduction cooled current leads for 50A with two heat sinks at 4-8K and 40-80K
- No gas flow
- Designed and fabrication of one prototype (for module 8) at CERN
- Heat loads at 50A (for each of the six leads)
 - 2.56 W/lead at 70 K,
 - 0.54 W/lead at 4.5 K,
 - 0.04 W/leads at 1.9 K
- At zero current load at 1.9 K will vary from 0.02 to 0.035 depending on the length



Lead Design for Module 8




3/28/2007

H. Brueck. MKS-4


26



Mock-up at an earlier stage





XFEL Lead Design (proposal)



- Details need to be discussed with CERN

Alternative HTS leads

- Alternative design
- Present problems are:
 - The temperature at warm end
 - Connect to 40-80K by copper braid
 - 77K cannot be realized by a reasonable copper section
 - Supporting
 - Forces due to movement during cool down



Status of the Current Lead Assemblies


- Prototype ready by the end of this month ([details](#))
- Some parts to connect the lead assembly to the vacuum tank have to be manufactured here at DESY
- We plan a meeting end of September at CERN to discuss
 - the implications due to the design changes for the “final” XFEL module version
 - Who will update the design drawings for series production
 - Where we can produce more prototype assemblies
- The ordering of the HTS lead assembly is delayed
 - Best is to order a “preliminary” assembly to test it at DESY

Plans for Testing

- Tests of each magnet and each lead assembly **warm** and **cold**
 - Prototype phase
 - Series production phase (at rate of 1 magnet and 1 lead per week)
- Need a special cryostat only for these tests
 - Equipped with an anti-cryostat to allow for a warm measurement systems inside of the cold magnet
- Decision taken to build a cryostat in H55 (cold HERA magnet test area) using existing installations and cryo connections to the HERA cryo plant
- Need new test benches and equipment for **warm** and **cold** tests


Test Area in H55

- Cryostat close to HERA test stand
- HERA measurements still possible
- Special adapter with flexible connection to cryostat
- Pump for 2K, 30mbar operation
- Timescale:
 - Specifications are in preparation
 - Place order by end of 2006
 - **Installation in autumn 2007**



Cryostat Proposal

- Vertical cylinder with access from top
- Magnet preinstalled and aligned on support outside
- Support with magnet mounted in cryostat always in the same position
 - Then no precise alignment necessary
 - Only for some magnets precise alignment with respect to stretched wire system
- Connections leads-tank, lead magnet are **not** welded but sealed by Aluminum rings instead
- Tests of magnet and current lead assembly at the same time



Magnet Tests in H55 “warm”

- Tests at room temperature on special test bench
- Harmonic measurement with coil to check field quality ([info](#))
 - collaboration with IHEP Beijing, building pickup coil
- Axis and angle with “stretched wire” ([info](#))
 - Reference magnetic centre w. r. t. mechanical centre (left/right)
 - Details need to be discussed with alignment people
 - Preparation of the connection to the BPM
 - Required accuracy 0.3mm for axis offset and 3mrad for roll angle difference for arbitrary pairs
 - Measure offset of mag. Axis w. r. t. to alignment plates ([sketch](#))
 - Drill precise holes for dowel pins on milling machine using the alignment plates


Status of the Preparation for Tests

- Setting up for warm measurements
 - A new harmonic coils measurement system especially for short magnets with a large bore
 - Based on the “Chinese coil”
 - A new measurement table to hold the magnet, the harmonic coils system and the stretched wire system
- Preparing for cold measurements in H55 for winter 2007
 - Need to design and order new components

End


Measurement Coil

- Warm bore inner diameter $63.5 - 2 * 1.6 = 60.3\text{mm}$
 - 6.9mm radial for MLI and iso-vacuum
- Coil OD up to about 59mm:
 - Either long coil with bearings outside
 - Bending problem
 - Or short coil with bearings inside
 - Support and drive
- Magnet length 300mm (TTF quad doublet 570mm)
- Cryostat diameter at measurement pipe 1200 or less
 - At least magnet length + ~200mm




$$\text{ID } 77.3 - 63.5 \Rightarrow 13.8\text{mm}$$

$$\Rightarrow 6.9\text{mm}$$




Status at CERN

- available at CERN
 - Brass rods, and are copper plated at CERN
 - Stainless steel pipes
 - Inserts were manufactured and are ready to be welded to the tubes
 - The two stainless steel flanges needed for one assembly are available
- Kapton tubes were ordered and they will be at CERN by end of September
- The PEEK flanges are going to be machined in September
- The optimization of the process for the EBW of the braid at the warm end of the lead was made: it was performed on some samples, where very good results were obtained
- One assembly could be completed by end of September- beginning of October
- A nice mock-up of the assembly that proves the feasibility of the shaping of the conductors was made
- Meeting sometime in October
 - By then, we should be able to have a look at the first assembly
 - There are also some few points that we would like to be discuss
 - thermalization blocks, fixation of warm terminals, tests to be made on the prototypes



Quadrupole Production 1




3/28/2007



H. Brueck. MKS-4

40


Quadrupole Production 2



Dipole Production 1



Dipole Production 2



3/28/2007

43