


The SLC

**N. PHINNEY
SLAC**

**SLD Collaboration Meeting
San Francisco, California**

October 5, 2001



SLC Overview

SLC is unquestionably the most difficult accelerator ever operated

The challenges were grossly underestimated
the delusion of a quick, cheap triumph like SPEAR persisted for years in spite of overwhelming evidence to the contrary

SLC also had more near-death experiences than any other accelerator
successive HEPAP subpanels called for termination only to see it rise from the ashes

The world-class physics that eventually came out of the SLD program is a triumph
due to years of hard work and innovations by countless people

All TeV linear collider proposals build on the knowledge and experience from SLC

Luminosity

$$L = \frac{N^+ N^- f}{4 \pi \sigma_x \sigma_y} H_d$$


	Design	1998
Repetition rate, f (hz)	180	120
Intensity, N (10^{10})	7.2	4.0
σ_x (μm)	1.65	1.5
σ_y (μm)	1.65	0.65
$\sigma_x * \sigma_y$ (μm^2)	2.7	1.0
Disruption factor, H_d	2.2	2.0
Luminosity($10^{30}/\text{cm}^2/\text{sec}$)	6.0	3.0

SLC History

1979	First proposed, began design studies	
1985-87	Construction	
1989	1st Z in Mark II detector on April 11 Mark II run to Nov, 1990	~1200 Zs
1991	SLD engineering run	~300 Zs
1992	1st SLD Physics Run Electron polarization	10000 Zs 22%
1993	SLD Physics Run switched to Flat Beam optics Strained lattice cathode	50000 Zs 62%
1994-5	SLD Physics Run Major upgrades to Damping Rings and Final Focus Thinner layer cathode	100000 Zs 77%
1996	Short SLD Physics Run with new Vertex Detector VXD3	50000 Zs
1997-8	Major SLD Physics Run with VXD3	> 350000 Zs

SLC <-> NLC

1992 - 1998 SLD Luminosity



SLC 1980

Richter returned from sabbatical at CERN

where he had convinced them to build LEP
and started the SLC as competition

First step - 10 sector 'feasibility test'

damped e- bunches → BL90 analyzer

Construction started on SLC injector

CID - Collider Injector Development

South Damping ring - (was to be 2 in 1 vault)

Linac upgrade - klystrons, quads, correctors

Breidenbach began building control system

with Grp C staff - Siegrist, Jobe, others

+ new hires - Sheppard, NP, Bogart, Thompson

modernizing SLAC controls was a challenge

pre-Ethernet, VAX 11-780 1 Mbyte

“Computer” was hated as interference

Operations green-thumb, not model-based

SLC 1984

Richter became SLAC director

Rae Steining took over SLC project

Damping Ring commissioned

large diverse team - many now elsewhere

Delahaye (SL Division head, CERN), Jowett

Wiedemann (SSRL)

Ruth, Chao, Raubenheimer, Ross, etc. SLAC

(later) Hutton (Accel. Dept head, TJNAF)

SLC Design Handbook published

ed. R. Erickson

design current $5.0 \rightarrow 7.2 \times 10^{10}$ @ last minute

due to SR emittance growth in Arcs

SLC Construction authorized

ARCs & Final Focus

Positron Production, 2nd Damping ring

SLC 1987 - 1988

1987 - Construction complete

magnitude of problems began to be apparent

ARCs - 1st beam revealed major problems

optics errors + terrain-following rolls

“PhaseFix, RollFix, RitFix, SkewFix, ...”

ArcBusters - Barklow, Emma, Walker, Krejcik (1990)

January, 1988 - Mark II moved on beamline

Steining headed new Accelerator Department

Memo by R. Steining

On April 6, 1988, both beams were brought simultaneously through the IP into dumps. The number of e^+ and e^- per pulse were 0.3 and 0.5 10^{10} , at a repetition rate of 10 pps.

The background in the Mark II detector has been analyzed. The main problem ...(is) muons. ... additional collimators ... should cut the background to a level which will allow operation ... with currents $1.0 \cdot 10^{10}$ in each beam.

August 1, 1988 - Emergency Task Force

Richter led SLC, Breidenbach led controls,
Schalk led software, Steining left SLAC

SLC 1989 - 1991

April 11, 1989 - 1st Z detected by Mark II

October, 1989 - Task force disbanded

Mark II had ~ 500 Zs

LEP had begun physics in September, 1989

Loma Prieta earthquake

December, 1989 - SLC 'White Paper'

Breidenbach, Burke, Himel, Paterson,
Ruth, Seeman, Sheppard

1991 ... will be the first full year of physics running with the new detector, the SLD. The integrated luminosity goal for 1991 is 10^5 Z particles with polarized electrons.

August, 1990 - Program Coordinator (NP)

balance conflicting Mark II/ PEP/ SLD needs

November, 1990 - Mark II Run ended

Record day was 15 Zs on tape

PEP physics program terminated

January, 1991

100-year freeze - December 23, 1990

SLC Steering committee formed

SLC PERFORMANCE IN 1991

**M. Breidenbach, D. Burke, T. Himel,
J. Paterson, J. Seeman, J. Sheppard, R. Ruth**

**December 1989
Revised January 1990**

TABLE I.E.1. SLC PERFORMANCE & GOALS

	Independent Parameter Targets ^(a) for 1991 Program	Achieved in 1989	1990	Possible Scenarios for 1991 Parameters		
				(A)	(B)	(C)
Intensity at IP						
$N^-(10^{10})$	6	2	3.5	4	5	5
N^+	6	1.3	2.5	3.5	4	5
Rep. rate	120	60	120	120	120	120
Effective emittance at IP ^(b)						
$\epsilon_x^-(10^{-10}\text{rad}\cdot\text{m})$	4	6	6	4	6	5
ϵ_y^-	3	5	5	3	4	3.5
ϵ_x^+	4	6	6	4	6	5
ϵ_y^+	3	5	5	3	4	3.5
Beam divergence at IP (μrad)	350	220	220	300	300	300
Beam size effective ^(c)						
$\sigma_x (\mu\text{m})$	1.7	3.3	3.3	1.7	2.55	2.1
σ_y	1.34	2.7	2.7	1.34	1.56	1.4
Pinch enhancement		1.0	1.0	1.15	1.1	1.2
Luminosity ($10^{30} \text{ cm}^{-2} \text{ s}^{-1}$)		0.014	0.094	0.67	0.52	0.97
Events/hour		1.6	11	79	62	113
Efficiency (short term) ^(d)		0.25	0.3	0.5	0.5	0.4
<u>Effective rate</u>						
Events/day		9.6	79	947	750	1090
No. of scheduled days of operation		160	120 ^(e)	250	250	250
No. of days for accel. dev. & maint.		30	40	100	50	100
No. of days data taking		130	80	150	200	150
<u>Number of Z's^(f)</u>		<u>624</u>	<u>3.2K</u>	<u>71K</u>	<u>75K</u>	<u>81K</u>

SLC Steering Committee

Nan Phinney - Chair

Bill Ash, Stan Ecklund, Tom Himel
Marc Ross, Ron Ruth, John Seeman
John Sheppard, Bob Siemann, Nick Walker

CHARGE TO THE COMMITTEE :

PLANNING AND COORDINATION OF 1991 RUN

- 1) Develop a Run Plan in coordination with the SLC system physicists which sets realistic and measurable goals and milestones
- 2) Review Projects critical to meeting those goals and ensure that sufficient resources and priorities are assigned
- 3) Review and Approve Machine Development Experiments
- 4) Develop a Weekly Run Schedule that includes goals, priority experiments, alternative backup experiments, and SLD time
- 5) Review the Progress of the Run and make necessary midcourse corrections

Steering Committee Impact

Detailed analysis of each run

what went wrong? right?

Careful planning of turn-on & machine dev.

step by step commissioning schedules

MD in 2-4 day blocks - limit edge effects

Focus on highest priority issues for luminosity

Backup MD list - use serendipitous downtime

Added resources to critical areas from Accelerator Theory & SLD

Positron Task Force - Siemann/Krejcik

Fast Feedback - Himel/Rouse

Damping Ring Upgrade - Siemann/Limberg

Final Focus Upgrade - Walker/Irwin

Broad-based attack on reliability issues

Breidenbach/Ross/Ops maintenance, etc.

Rigid control of maintenance activities

Repair Opportunity Day approval/signoff

SLC/SLD 1991 - 1993

Steady progress

Numerous improvements each year to
hardware, tuning, diagnostics

Much time/effort for machine development

Set achievable goals and met them

1991 - SLD Engineering Run

Goal 3-500 Zs Delivered 350 Zs
Achieved 3 * 1990 Luminosity/pulse

1992 - 1st SLD Polarized Run

Goal 10K Zs Delivered 11K Zs
Achieved 4 * 1991 average Luminosity
10K Zs won dinner bet with O'Fallon, Hess

1993 - SLD Run

Goal 50K Zs Delivered 50K Zs
Achieved 2-3 * 1992 Luminosity

1991 Run - May-August

Turn-on started before SLD installation complete
allow time for machine studies
SLD run started late July through August

Repetition rate limited to 60 hz by budget

Major improvements:

Positron yield stable at > 1.0 (task force)
factor of 2 at IP

Matching $\rightarrow$ linac to 2nd order (Emma)

Linac alignment, feedback, orbit bumps
(Seeman, Adolphsen, Himel)

ARC optics controlled (Barklow)

Superconducting FF triplets (Ash)
smaller β^*

+ dozens of minor upgrades

Machine uptime - 60%
(was $\sim 15\%$ in 1990)

SLC STATUS - 1992 RUN

January-February — Machine Startup
March - SLD Run — unpolarized
April — Polarized Gun Installation and Commissioning
May-August 15 — SLD Physics Run
August 15 - September — Increase Luminosity

Average Luminosity is $4 * 1991$

Z⁰s on tape / day is $5 - 10 * 1991$

Biggest gains have come from

- 120 Hz operation factor of 2
- Machine uptime 60-70 %
- Improved SLD/SLC Efficiency 70%
Better integration of machine and detector
- Improvements in intensity, emittance
control and tuning factor of 2

SLC Improvements for 1992

Injector

- New "Y" Installation for Polarized Source
- Sector 0 Klystrons upgraded to 5045s
- Subharmonic Bunchers treated with TiN

Damping Rings

- Aperture increase for South LTR transfer line
- Passive Cavity to damp π -mode Oscillations - (both rings)
- New radiation hard epoxy kicker for North Damping Ring
- Octupoles for improved matching in NRTL line

Linac

- Collimator to protect Scavenger Line Lambertson
- Cascaded Fast Feedback
- Post kickers to control Scavenger beam orbit

Arcs and Final Focus

- Movers for AGF magnets to fine-tune dispersion
- New technique for finding FF Sextupole alignment

Diagnostics

- Wire scanners for NRTL, SRTL, Positron Return Line
- Fast gated Camera for Synchrotron Light measurements

1993 Run - February-August

Plan for Higher Luminosity

Beam intensity 4×10^{10}

and/or

Flat beam Optics

DR microwave instability limited intensity to

3.2×10^{10} electrons at IP

3.1×10^{10} positrons at IP

Switched to Flat beams in mid-March

Achieved emittance ratio of 10:1

Best $Z_n \sim 6$ (1992 best 2.8)

Goal: 2000-2500 Z^0 /week on tape

Status: $> 700 Z^0$ /day on tape

Best 1992 - 315

4400 Z^0 /week on tape

Best 1992 - 1300

average 2500 Z^0 /week

Mini-Workshop on SLC Improvements

November 16, 19 & 23 1992

CID

- Possibilities for larger cathodes or longer pulses
→ full intensity with high polarization cathodes

Damping Rings

- New low emittance design
→ Reduce emittances by a factor of 3
→ Potential factor of 4 in luminosity

Final Focus

- Optics to correct 3rd order aberrations
→ Potential factor of 2 in luminosity

Multibunch Operation

- 2 or 3 bunches may be possible

.

Goal

- > 100-200 K Z^0 s/year in FY94

1994 Run

- Damping Ring Vacuum Chamber

Improvements:

- Raise threshold for microwave instability
- Reduce bunch length → better emittance
- Reduce energy spread → smaller IP size

Expected performance:

- 3.5-4 10^{10} per pulse at IP
- energy spread < 0.2 %

- Final Focus Optics Upgrade

Improvements:

- New quadrupoles and sextupoles to
reduce 3rd order aberrations
orthogonalize tuning
- New wire scanners to improve diagnostics
- Movers to align sextupoles

Expected performance:

- Vertical beam size 0.4-0.5 micron
- Peak Z_n → 10-15

Intensity

Difficult route to higher luminosity

SLC experience:

Each increase in bunch current means
new challenges

instabilities
wakefields = emittance growth
power handling

NLC learned this lesson early
design bunch intensity $\approx 1 \cdot 10^{10}$

1991 - limited by π -mode instability in rings

1992 - installed idling cavities
identified turbulent bunch lengthening
“sawtooth instability”

1994 - installed low impedance damping ring
vacuum chambers

SLC slowly increased the
bunch intensity to $\approx 4 \cdot 10^{10}$

Half of SLC design $\approx 7.2 \cdot 10^{10}$

pre-1994 Intensity Limit

“Flyer” pulses first seen by Mark-II in 1989


Energy-phase correlation diagnosed as
“doughnut effect” in 1991

Diagnostic signal of bunch length during store
revealed “sawtooth” instability in 1992

Threshold for instability $3 \cdot 10^{10}$ particles /
bunch in the damping rings

Instability causes phase jitter at extraction
which causes energy mismatch into the linac

Longitudinal Instability Mechanism




- Step changes in vacuum chamber generate wakefields that interact with short bunches

- Turbulent bunch lengthening is not smooth, but works like a relaxation oscillator

Sawtooth Instability

- . bunch length damps down after injection until threshold is reached
- . rapid (@ns) blowup in bunch length occurs
- . blowup is self limiting (nonlinear)
- . bunch damps until threshold reached again



Remedy for Raising the Intensity Limit

- Replace chamber with smooth pipe to raise threshold for instability by a factor 2

Pulse-to-Pulse Beam Jitter

RMS jitter at IP - 0.3-0.8 sigma

Some problems/solutions:

Quadrupole vibration

Feedback system performance

Long Range Wakefields (1995)

Calculations:

Predicted no problem

Observations:

Linac amplified jitter by factor of 6

e⁺/- jitter correlated

e⁻ jitter reduced factor of 2 if no e⁺ beam

Experiment:

Measured e⁻ oscillation vs e⁺ oscillation

Verified dependence on bunch spacing


Solution:

Split-tune lattice reduced coupling

e⁻ vertical jitter reduced by 30-50%


Long Range Wakefield Kicks in the SLC Linac

SLC-Design Lattice:



16-DEC-94

Split-Tune Lattice:



15-MAR-95

SLC Progress was due to

People

100s of Physicists and Engineers
Many now leaders at other facilities

Tuning Techniques

Many innovative ideas


Diagnostics

High precision, non-invasive, distributed
Monitoring and Trouble-shooting

Controls

Feedback, Automated procedures
Comprehensive Historical Data for analysis

End of Linac Beam Profiles



Colorized digital images of single pulses
analysed and displayed real-time

SLC LUMINOSITY

IMPROVEMENTS

**Progress due to development
of techniques for**

Emittance Control

Tuning Algorithms

Stabilization


Key elements were

Diagnostics ~ 60 wire scanners

Beam-based Feedback


> 50 systems, controlling > 200 parameters

*e⁺ BEAM PROFILES MEASURED BY WIRE SCANNERS
AT INJECTION INTO LINAC BEFORE SEXTUPOLE OPTIMIZATION*



Beam Size Monitor Evolution

- **1st wire scanners installed in 1990**
could measure Linac e^+ for 1st time
- **Total of > 60 scanners installed**
- **Emittance analysis tools (including skew)**
- **Jitter compensation**
- **Hands off procedure [®] history**
scheduled scans, robust analysis
- **Multi-detector scan [®] measure tails**
- **Hardware issues - wire size, breakage**
- **Laser wire [®] measure single beam at IP**
needed for NLC beam sizes
- **Breakthrough in last run**
tune Linac ϵ on FF wires (SLD On)



5722A7

Tuning Issues

(selected highlights)

- **New beam-based alignment techniques**
including FF sextupoles & octupoles
- **Optics & dispersion matching algorithms**
- **4-D transfer matrix reconstruction - Arcs**
including synchrotron radiation ϵ growth
& effective spin tune to preserve P_e
required HEP-style error analysis (Barklow)
- **2-beam dispersion free steering - Linac**
later applied at LEP
- **Emittance control techniques**
linac ‘bumps’ $\rightarrow$ cancel wakefield effects

All LC designs incorporate these methods

SLC provided 10 years of experience

® confidence in NLC

Stability Issues

**Linear Colliders are inherently
less stable than storage rings**

Each pulse is an injected pulse

Real-time Monitoring

**Tracking Changes
Studying Correlations**

® Improvements

Feedback Systems


**Control Energies and Trajectories
Maintain Collisions
Stabilize Polarized Source
Beam Optimization**

SLC had

**> 50 Feedback Systems
Controlling > 200 Parameters**

Feedback Evolution

- **1st ‘slow’ energy/orbit feedback in 1985**
- **Prototype pulse-to-pulse systems in 1987**
used dedicated hardware at end of Linac
- **Pulse-to-pulse collision feedback in 1989**
- **Generic ‘fast’ feedback in 1991-93**
database-driven, shared hardware
‘easy’ to add a new system anywhere
Linac systems connected by adaptive cascade
- **Expanded online diagnostics**
history, monitoring, FFTs
- **Luminosity optimization feedback in 1997**
dithering, >1K pulse averaging
- **Emittance optimization attempted**



1994 Performance

Integrated Luminosity

Goal:

> 100 K Z_0 s - > SLD

Total : > 100,000 Z_0 on tape
with ~80% polarization

DR and FF upgrades
100 nm Strained lattice cathode

Goal:

—> 4000-5000 Z_0 /week on tape

Status:

> 1500 Z_0 /day on tape

Best 1993 was 722

> 7000 Z_0 /week on tape

Best 1993 was 4400

average ~ 4000 Z_0 /week

-

SLC post-1995

SLD million Z run with VXD3 had been
approved in November, 1993
to start with 1996 run

SLC delivered 100K Z goal in 1994 run but
required extension through February, 1995
Longer than expected to see benefits from DR
and FF upgrades, minimal future upgrades

SLC schedule severely impacted by budget cuts,
also time for FFTB and ASSET runs

PEP-II construction had started
had priority, people and resources and
by 1996 required time for commissioning

1996 SLD run scheduled only Feb - June
NDR fire & vent in February, 1996

→ 50K Zs in 2.5 months

SLC 1997-98

Support from SLAC management was luke-warm
at best - focus on PEP-II

SLC/SLD agreed to all out luminosity push
not much to lose !!!

Concentrated on low-cost, targeted upgrades
i.e., relocating existing hardware

ARDA created Task Force (Irwin/Zimmermann)
+ help from SLD (Bogart/Russell)

Many clever new ideas from NLC and SLC2000

GOAL: more than Double previous Luminosity

Made “Hail Mary” play at April, 97 DOE review
this successfully got SLD funding to run
through mid-1998

Luminosity Projections

With 1996 parameters- intensity, emittance

$$\begin{array}{llll} N^- & = 3.8 & N^+ & = 3.6 \quad 10^{10} \\ \epsilon_x & = 5.5 & \epsilon_y & = 0.9 \quad \text{in S28} \end{array}$$

$$\begin{array}{ll} \text{Expected} & = 150 \text{ Z/hr} \\ \text{Achieved} & = 120 \text{ Z/hr (peak)} \\ & 60 \text{ Z/hr (typical)} \end{array}$$

With same parameters, larger Θ_x , larger H_D

$$\begin{array}{llll} \Theta_x & = 475 \mu\text{rad} & H_D & = 1.9 \\ \text{Expected} & = 250 \text{ Z/hr} \end{array}$$

Improved IP tuning and wakefields

$$\text{Typical (?) } = 150 \text{ Z/hr}$$

With better Linac values- intensity, emittance

$$\begin{array}{llll} N^- & = 4.2 & N^+ & = 4.0 \quad 10^{10} \\ \epsilon_x & = 4.0 & \epsilon_y & = 0.6 \quad \text{in S28} \\ H_D & = 2.2 & & \end{array}$$

$$\begin{array}{ll} \text{Expected} & = 500 \text{ Z/hr} \\ \text{Typical (?) } & = 250\text{-}350 \text{ Z/hr} \end{array}$$

Goal: 250 Z/hour or Bust

Raimondi & Usher

Led the effort to double luminosity

bold, brilliant ideas, endless hours @MCC

1. Produce smallest possible IP spots

New tuning techniques in RTL, Linac, Arc, FF

Demagnification moved closer to IP, stronger

Soften FF bend by misaligning quads (Xmas)

New PM octupoles (3/98 - \$10K each)

2. Control backgrounds so not limitation

Spare DR sextupoles in BSY

FF colls moved to 45° in Arc Reverse Bend

3. Improve stability & reproducibility


facilitate quick recovery, average → peak

10K/week in November, 1997 (Richter party)

15K/week in March - 20K/week in May, 1998

Run ended abruptly 1 wk early with e⁺ leak after
all time record shift of > 2K Zs (250/hr * 8)


SIMULATION OF σ_x vs θ_x^*



P. RAIMONDI

15

SIMULATION OF σ_y vs θ_y^*
SHOWING EFFECT OF OCTUPOLES



ABERRATIONS TO BE CANCELLED


$$U_{3246} \Rightarrow \Delta y \propto \Delta x' \Delta y' \left(\frac{\Delta E}{E} \right)$$

$$U_{3444} \Rightarrow \Delta y \propto \Delta y'^3$$

M. WOOLEY

13e

IP Beam Size vs Time



Disruption Enhancement (aka Pinch Effect)

1998 parameters:

$$\begin{aligned}\Sigma_{x,y} &= 2.1, 0.9 \mu\text{m} & N^{+/-} &= 4.0 \times 10^{10} \\ \theta_{x,y}^* &= 450, 250 \mu\text{rad} & \sigma_z &= 1.1 \text{ mm} \\ H_D &= 2.1 \text{ (predicted)}\end{aligned}$$

With these beams,
disruption enhancement is significant


Ratio of luminosity recorded by SLD detector
to luminosity predicted for rigid beams

$$H_D^{meas} = \frac{L_{SLD}}{L_{SLC}^0}$$

In excellent agreement with H_D^{theory}

Measured enhancement > 100%

SLD Measured Luminosity from Zs & Bhabhas /
Luminosity Calculated **without** Disruption



1997-98 SLC Run

Peak luminosity 300 Z⁰s / hr
 3 10³⁰/cm²/sec

3 times previous record

Integrated luminosity 350,000 Z⁰s
≈ double total from all previous runs

Beam size 1.5 by 0.65 μm
3 times smaller than design

Disruption enhancement 100%

Luminosity steadily increased throughout run

Gains from improved tuning procedures
And reconfiguring existing hardware
with NO major hardware upgrades

SLC continued to provide valuable experience
—> future linear colliders

SLC LESSONS

**With a New Accelerator technology
expect a lot of hard work
and surprises**

(examples: SLAC Linac, storage rings, SLC)

**The most difficult problems are
usually those which were
not expected**

**Diagnostics - best/most possible
Feedback**

Powerful, flexible control system

**Discipline of trying to produce physics
forces you to
discover and solve problems
not required for a test project**

SLC Luminosity History

